# Expansion of Existing Facility into Wave Energy Test Site (WETS) Marine Corps Base Hawaii (MCBH)

**Briefing to:** 

**US Department of Energy (DoE)** 

By:

Hawaii National Marine Renewable Energy Center (HINMREC)

Hawaii Natural Energy Institute (HNEI)

University of Hawaii (UH)


February 13, 2011

# Wave Energy Test Site (WETS)

- Objective: Expand infrastructure from one → three<sup>+</sup> grid-connected test berths;
- Presently: submarine power cable; data collection system; single "40 kW" OPT buoy 1200 m offshore, 30 m depth; 4<sup>th</sup> Generation Operational (12/09); Grid(9/10) → Could accommodate one more WEC Device @ 30 m;
- Expansion: Additional submarine power cable →
   Deeper waters 50 m 100 m → Two more WECs →
   Capability to test ≤ 4 WECs at 30m to 100 m depths.



# MCBH at Kaneohe Bay



### **Project Location Accessibility & Workability**

- Heeia Kea Boat Harbor: medium sized work-boats;
- Kaneohe Bay: calm berthing for larger work-boats;
- MCBH Fuel Pier: staging (vessel berthing, dive & welding equipment) and mobilization of OPT equipment (WEC Buoy, transformer pod, subsurface float);
- <u>Proposed WETS</u>: work-boat moored in K-Bay with WEC devices assembled and deployed from Fuel Pier;
- WETS Accessibility: Year round Install &
   Maintenance ops up to 3' Swells and light Trades;
   and, Inspection & some Maintenance up to 6' Swells.

### **Deployment Images**




"40 kW" Point Absorber Buoy


• 3<sup>rd</sup> Generation Operational since December 2009

• Grid-Connected September 2010

**OCEAN POWER TECHNOLOGIES** 



- Existing WEC
  Device Test Site at
  MCBH (Kaneohe
  Bay);
- -Subsea Cabling Installed 2003;
- 3<sup>rd</sup> Generation 40 kW Point Absorber Operational.



### **WETS**

Ocean Test Area: 4.92 km<sup>2</sup>

- Black trapezoidal area set aside by Navy/USMC;
- To be surveyed by HINMREC/HNEI
- "Yellow dot" Existing OPT Buoy
- Depths in meters

### **Beyond WETS**

- Could Enclose: ~ 70 MW Wave Farm-Array

# Why WETS?

### USN:

- President's Executive Order 13123 → development of renewable power resources at federal installations;
- U.S. Federal Energy Policy → reduce the nations dependence on foreign oil.

### DoE:

- Implement Test Sites for Wave Energy Conversion (WEC) Devices in the USA.

# Why WETS at MCBH?

### <u>Technical</u>:

- Expanding Existing Navy/USMC Site vis-a-vis Implementing a New Site elsewhere;
- Hawai'i Pertinent Ocean Eng. Facilities & Site Specific
   Deployment & Maintenance Experience (since 2003);
- HNEI in position to manage site.

### Licensing & Permitting:

- New-Site > 24-months and challenging;
- Expansion < 12-months: (i) NEPA Process similar to 2003
   <p>Navy EA/FONSI; (ii) Federal & State Agencies defer to USN FONSI; (iii) FERC License not required because power delivered to DoD Installation.


# Why WETS at MCBH?

### Funding:

- Leverage DoE/USN Funds;
- Navy processing environmental permitting for expansion;
- DoE funding of detailed bathymetric and bottom survey to be funded through HINMREC.

### Wave Power Flux (kW/m) Monthly Average:

- Commercial Sites (Reedsport, OR; Pa'uwela, HI)
  - •Test Site (Kaneohe, MCBH, Oahu)



### MCBH Installation & Maintenance Infrastructure Available

{WEC Device Specific Since 2001; 4th Generation OPT Buoy}

### <u>Installation</u> (workboats, divers & experienced crew)

- Submarine power and data cables;
- Cables landing & Grid interconnections;
- Mooring systems;
- WEC Devices Deployment, Commissioning and Retrieval.

### **Fabrication**

Several Steel & Al Shops, Honolulu Harbor side.
 PTO/Electronics proprietary

### **Maintenance**

- Minor: in-situ at MCBH
- Major: e.g., Pacific Shipyards Int. Dry-docks & Builder of SWATH ships, Tanker Mooring Buoys

### **Current Tenant (OPT): Test Site Assessment**

- Site ideal for experimental and prototype at-sea tests wave resource is adequate for testing; and, maintenance ops are feasible year-long;
- Deployment only authorized (US Army Corps) during summer months at commercial sites in Hawai'i (Pa'uwela) and Oregon (Reedsport);
- WEC device can be located in fairly deep water, without long power cabling to shore;
- Hill/Bunker at MCBH allows for visual/camera observation and communications (direct line of site) without a tower;
- MCBH a willing customer;

14

### **Current Tenant (OPT): Test Site Assessment**

- MCBH supportive of renewable energy development;
- •Dive operations for inspections enhanced with extensive underwater visibility in Hawaii;
- Mokapu Waverider (wave measurements) buoy supported by UH;
- UH staff experience in ocean eng & oceanography;
- •Well developed transportation infrastructure to and between the islands for equipment deliveries. Test Site is relatively close to Honolulu Harbor;
- •Private Sector Support: Ocean Engineering firms available with ten year experience supporting OPT in Assembly, Deploy, Install, Maintain, Repair and Retrieve.

## WETS Implementation: Tasks

### **Funded Tasks**

- HINMREC /NFESC Environmental Studies → EA/EIS input;
- NFESC Amended EA/FONSI → multiple test berths 30 m to 100 m depth.

### **Ongoing**

• **UH/HNEI** - Coordinate DoD, DoE, State partnership to develop Congressional support & funding for Expansion (~ \$9 M Required).

### **WETS Modus Operandi**

- Navy/MCBH provide/host test site, use/purchase power;
- HNEI Operate & Manage WETS (~\$ 1 M/year Required);
- Developers Responsible for: device, mooring, connection to socket, user fee (plug & test), data acquisition & shore controls.

### **WETS at MCBH: Timeline and Partners**

	2010	2011	2012	2013	2014
OPT Experimental Point Absorber Buoy					
WETS CONCEPT DEFINITION	UH/NFESC	]			
WAVE RESOURCE & PRELIM BATHYMETRY	UH				
IDENTIFY & ADVICE WETS USERS	UH	UH			
FIELD SURVEY: DETAILED BATHY & BOTTO	DM .	UH/NEPA	l		
FINAL DESIGN		NFESC/UH	l		
EA/FONSI AMENDMENT & PERMITS		NFESC			
ACQUISITION & CONSTRUCTION			TBD	TBD	İ
OPERATIONS					TBD/UH →

UH: University of Hawaii National Marine Renewable Energy Center. Tasks funded by DOE

2010-2012: \$215 K for Permitting & Environmental; \$180 K Eng. Support.

2013-2014: \$125 K Expected for Additional Eng. Support

UH/NEPA: Tasks require NEPA Compliance Authorization

NFESC: Naval Facilities Engineering Service Center. Tasks funded by NAVFAC

TBD: Funding Source to-be-determined. Budget estimated at \$9 M. Currently \$0.28 M from DOE; plus \$0.17 M expected 2013-2014

TBD/UH: UH to Manage Upgraded Test Facility. \$1 M Annual Budget Estimated. Funding Source to-be-determined

# WETS Schedule Summary

- <u>Task</u> Upgrade Navy infrastructure from <u>1</u> into <u>3</u><sup>+</sup> socket berths ready for WECs to *plug & test*.
- <u>Team</u> (i) <u>Navy</u>: amend EA/FONSI (ongoing); Final WETS Design (pending); Infrastructure (pending);
  - (ii) <u>UH</u>: Resource & Prelim Bathymetry (done); Concept Definition (done); Identify/Advise developers (ongoing); Detailed Bathy. and Bottom Survey (pending).
- <u>Budget</u> \$9 M Infrastructure & \$1 M/year for Ops (not available); only \$0.45 M from DoE for Infrastructure.
- <u>Timeline</u> EA/FONSI & Final Design by 12/11 on schedule but Infrastructure Funding not expected until 2013 the earliest.

# Summary

- Current DoE funding sufficient for laboratory testing, modeling, baseline environmental studies, and technical support by UH but not adequate to directly support technology development or pre-commercial in-water testing;
- HINMRE/HNEI has been unable to perform any field/survey work pending (~1-year+) NEPA Compliance Authorization from DoE;
- HNEI is working with Navy, DoE and State of Hawaii to identify WETS funding (~\$9M required for infrastructure; and ~\$1 M/year for operations).

# Annex

# WETS at MCBH DoE Funded Activities at HINMREC

### Phase I (Completed)

- Concept for multiple testing berths was developed (WETS), working with NFESC/NAVFAC;
- Potential users identified;
- Wave resource and preliminary bathymetry were documented.

### Phase II (Planned)

- Detailed Bathymetric Survey & Environmental/Other
   Studies as input to Amended EA and Permitting Process;
- Expanded WEC testing with the goal of establishing a WETS Facility (currently no funding for development).